

B0210 CESSATION OF ACTIVITIES

An outline decommissioning plan will be developed in conjunction with the O&M teams when they are mobilised prior to the commissioning phase of the project.

Based on historical data, site investigations and contamination testing carried out to date on site it is not anticipated that any land or ground water contamination will occur during decommissioning activities based on land usage to date. All hazardous material to be stored on the site during the operation phase of the project will have secondary containment and thus contamination of groundwater or land is not expected during the operation phase. During decommissioning, all of the secondary bunded areas will be assumed to be contaminated unless tested and proved otherwise. And will be disposed of appropriately

During decommissioning of the facilities waste materials and those for potential reuse or recycling will be sorted to minimise cross contamination between the groups of materials destined for different waste streams, this should ensure that the waste stream or reuse/recycling options chosen are the least environmentally onerous as possible.

All waste that is to be disposed off-site will be fully tested and sent to the appropriate waste disposed site based on the level of inert, contaminated or hazardous category tested.