

Quarry Dust Mitigation Plan

The following are the dust mitigation measures that shall be taken on site:

- The crusher is equipped with sprinklers for dust control.
- The screen's conveyors will be wet when required to control the dust emitted.
- The road on site from the gate to working area is currently covered with gravel, which periodically will continue to be topped up as required. The same road will also be sprinkled as required.
- The piles will be sprinkled when required during the summer period and depending on weather in winter.
- Stockpiles will be kept at the lowest possible.
- Near the gate, outgoing trucks' wheels will be sprinkled with water when needed.
- The site is equipped with a water tank to be used for wetting and for the above-mentioned purposes.