

Quarry Mitigation Plan

The following are the dust mitigation measures that shall be taken on site:

- The crusher is equipped with sprinklers for dust control.
- The scalper's conveyors will be wet at all time to lower the dust amount on site and piles will be soaked with water.
- The road on site from the gate to working area will be sprinkled as required.
- The piles will be sprinkled during summer period around 3 times/day and depending on weather in winter.
- Stockpiles will be kept at the lowest possible.
- Near the gate, outgoing trucks' wheels will be sprinkled with water when needed.
- The site is equipped with a water tank to be used for wetting.